



**PUDUVAI BHARATHIAR GRAMA BANK
HEAD OFFICE**

PRICE BID DOCUMENT FOR 45 KVA DG SET

PART - II

PRICE BID

**Tender Document for Supply, Installation, Testing and
Commissioning of One 45 KVA DG Set
for
Puduvai Bharathiar Grama Bank, Head office**

ISSUED TO

M/s. _____

This document contains 2 pages



**PUDUVAI BHARATHIAR GRAMA BANK, HEAD OFFICE
NO. 5, KAMARAJ SALAI, SARAM, PUDUCHERRY 605 013**

Bill of Quantities for Supply, Installation, Testing and Commissioning of a 45 KVA DG Sets for Puduvai Bharathiar Grama Bank, Head Office

PART II - PRICE BID

SI.No	Description	Qty	Rate	Total	GST %	GST	Total Cost
1	45 KVA DG Set Supply, installation in position, at the location indicated by the Bank, testing, commissioning and handing over of a diesel generator set of capacity of 45KVA, 3 phase, 415 volts, 50Hz (12 KW at 0.8 pf lag) complete with diesel engine, water cooled radiator, self starting device, batteries, battery charger, engine panel, base frame, anti-vibration mounts, diesel tank, acoustic enclosure, power control panel, suitable capacity 4P MCCB with overload protection and all connected accessories including standard set of tools and spares (to be supplied free of cost) complete as described in detailed technical specifications. The amount quoted shall be inclusive of following.	01 Set					
2	Earthing at GI Pipe 40mm Dia B Class - 3mtrs least at a depth of 10 feet and filling of alternate layers of charcoal and salt and making a 300mm*300mm chamber brickwork	04 Nos					
3	50 Sq mm 4 Core Alum Ar.Cable	15 Mtr					
4	End Termination	04 Nos					
5	8SWG Copper Wire	60 Mtrs					
6	2.5 Sqmm 6 Core Copper flexcable	10 Mtrs					
7	AMF Panel - 2 EB Source with by pass arrangement	01 No					
8	Transport and UnloadingCharges	01 Job					
9	Erection Charges	01 Job					
Total							